

CO₂ Reduction


Probing CO₂ Reduction Pathways for Copper Catalysis Using an Ionic Liquid as a Chemical Trapping Agent

Gui-Rong Zhang⁺, Sascha-Dominic Straub⁺, Liu-Liu Shen⁺, Yannick Hermans, Patrick Schmatz, Andreas M. Reichert, Jan P. Hofmann, Ioannis Katsounaros, and Bastian J. M. Etzold*

Abstract: The key to fully leveraging the potential of the electrochemical CO₂ reduction reaction (CO₂RR) to achieve a sustainable solar-power-based economy is the development of high-performance electrocatalysts. The development process relies heavily on trial and error methods due to poor mechanistic understanding of the reaction. Demonstrated here is that ionic liquids (ILs) can be employed as a chemical trapping agent to probe CO₂RR mechanistic pathways. This method is implemented by introducing a small amount of an IL ([BMIm][NTf₂]) to a copper foam catalyst, on which a wide range of CO₂RR products, including formate, CO, alcohols, and hydrocarbons, can be produced. The IL can selectively suppress the formation of ethylene, ethanol and n-propanol while having little impact on others. Thus, reaction networks leading to various products can be disentangled. The results shed new light on the mechanistic understanding of the CO₂RR, and provide guidelines for modulating the CO₂RR properties. Chemical trapping using an IL adds to the toolbox to deduce the mechanistic understanding of electrocatalysis and could be applied to other reactions as well.

Introduction

The electrochemical CO₂ reduction reaction (CO₂RR) provides a promising solution to offset the increased atmospheric CO₂ concentration, and also represents an excellent

How to cite: *Angew. Chem. Int. Ed.* **2020**, *59*, 18095–18102
 International Edition: doi.org/10.1002/anie.202009498
 German Edition: doi.org/10.1002/ange.202009498

option for storing intermittent renewable electricity (e.g. solar, wind energy) by producing value-added chemicals.^[1] However, poor energy conversion efficiency and broad product spectrum are major barriers to achieving economic viability of the CO₂RR. Intensive effort has been spent searching for high performance electrocatalysts.^[2] Copper (Cu) is identified as the only metal that produces hydrocarbons and alcohols with appreciable Faradaic efficiency (FE),^[3] due to its moderate binding strength with key intermediate species.^[4] Despite its unique catalytic properties, mechanistic understanding of the reaction pathways which provides the basis of steering the CO₂RR toward desired products, remains controversial. Although the adsorbed *CO species is well-accepted as a key intermediate leading to various C₂₊ products, it remains an open challenge to elucidate the mechanistic pathways from *CO to C₂₊ products on Cu. Especially, the formation mechanisms of ethylene and ethanol have long been the subject under debate in both experimental and theoretical studies.^[5]

Mechanistic understanding of the CO₂RR are derived almost exclusively through in situ/operando spectroscopic techniques (e.g., IR, Raman).^[6] Early in situ spectroscopic studies of Cu electrodes suggest that hydrogenation of *CO to *CH₂ would be the precursor to ethylene and ethanol,^[6c,7] while others suggest that formation of these C₂ species would mainly proceed through forming a *CO dimer (*C₂O₂⁻) which is subsequently protonated to *CO-COH.^[8] These discrepancies may stem from the inherent limitations of spectroscopic techniques. The limitations include the interference from the solvent or spectator species,^[8b,9] limited temporal/spatial resolution due to the low coverage and short residual time of key intermediates,^[6c,d] and ill-defined background signals that are sensitive to electrode pretreatment history and cell configurations,^[6d,10] and all these may add to the uncertainty of the measurement and make interpretation of resultant spectra a non-trivial task.^[6d] Complementary ways of analyzing the CO₂RR mechanism are highly desirable.

Chemical trapping is regarded as an effective way to study reaction mechanisms. It originated in organic chemistry and was widely applied in catalysis.^[11] The reaction mechanism is deduced using a compound (trapping agent) that reacts specifically with one or more reaction intermediate(s) to form a stable product(s). The trapping agent stops/decelerates specific reactions, and reaction mechanisms can then be deduced by examining the products. Bell et al. demonstrated in their exemplary works that the production of hydrocarbons from CO hydrogenation involved adsorbed methylene species as a key intermediate, as shown by the suppressed formation

[*] Dr. G.-R. Zhang,^[+] S.-D. Straub,^[+] Dr. L.-L. Shen,^[+] P. Schmatz, Prof. B. J. M. Etzold
 Ernst-Berl-Institut für Technische und Makromolekulare Chemie,
 Technical University of Darmstadt
 Alarich-Weiss-Str. 8, 64287 Darmstadt (Germany)
 E-mail: bastian.etzold@tu-darmstadt.de

Dr. Y. Hermans, Prof. J. P. Hofmann
 Surface Science Laboratory, Department of Materials and Earth
 Sciences, Technical University of Darmstadt
 Otto-Berndt-Str. 3, 64287 Darmstadt (Germany)

A. M. Reichert, Dr. I. Katsounaros
 Helmholtz-Institute Erlangen-Nürnberg for Renewable Energy (IEK-
 11), Forschungszentrum Jülich GmbH
 Egerlandstraße 3, 91058 Erlangen (Germany)

[+] These authors contributed equally to this work.

 Supporting information and the ORCID identification number(s) for the author(s) of this article can be found under:
<https://doi.org/10.1002/anie.202009498>.

 © 2020 The Authors. Published by Wiley-VCH GmbH. This is an open access article under the terms of the Creative Commons Attribution License, which permits use, distribution and reproduction in any medium, provided the original work is properly cited.

of hydrocarbons in presence of methylene scavengers.^[12] This chemical trapping method has not yet been applied to electrocatalysis, largely due to the lack of suitable chemical trapping agents that can selectively interact with specific intermediates without being oxidized/reduced under electrochemical conditions. Inspired by previous works where ionic liquids (ILs) were employed as surface modifiers to modulate the catalytic properties of a variety of electrocatalysts, an IL is used here as a chemical trapping agent to analyze the CO₂RR pathways in Cu catalysts. This idea is realized by analyzing the IL-induced perturbation in the product spectrum. The rationales for choosing ILs also include their coordination ability with CO₂RR intermediates and good stability over a wide potential window.^[13] ILs have been used as either pure electrolyte or electrolyte additive to change the CO₂RR properties in various metal catalysts (e.g., Ag, Pb).^[14] ILs are reported to lower the overpotential and explicitly favor the formation of CO, presumably through coordinating with reduction intermediates (e.g., CO₂⁻) by either stabilizing the intermediates or preventing their spatial approach.^[13c,15]

In the current study, the IL is introduced by immobilizing a small amount of 1-butyl-3-methylimidazolium bis(trifluoromethylsulfonyl)imide ([BMIm][NTf₂]) on a Cu-Foam catalyst (see Figure S1 in the Supporting Information). This method follows the concept of “solid catalyst with ionic liquid layer (SCILL)”, which was first invented in heterogeneous catalysis,^[16] and was soon successfully transferred to electrocatalysis particularly in improving electrocatalysts for the oxygen reduction reaction (ORR).^[17] The hydrophobic nature of the IL and capillary force ensure the confinement of the IL within the catalysts even in aqueous electrolytes.^[17de] We demonstrate that IL can act as a chemical trapping agent in the CO₂RR. Its presence significantly alters the product spectrum by selectively suppressing the formation of ethylene, ethanol, and n-propanol, without disturbing either FE or partial current density of the others. These findings demonstrate selective interactions between the IL and one or more reaction intermediate(s), while the altered product distribution provides a unique perspective to track the CO₂RR pathways. This work may represent a simple approach to gaining mechanistic insights into the CO₂RR, and also paves a new way in modulating the CO₂RR activity and selectivity.

Results and Discussion

Cu foams were chosen because of the unique catalytic property of Cu and the abundance of porous structure which is beneficial to IL immobilization. Cu-Foams were prepared using a hydrogen evolution reaction (HER) assisted electrodeposition method,^[18] with a Cu plate as the substrate and copper sulfate as the precursor (Figure S2). [BMIm][NTf₂] was chosen because of its hydrophobic nature and ability to coordinate with CO₂ and/or its anion radical.^[15,19] Figure 1 a displays the representative scanning electron microscopy (SEM) image of pristine Cu-Foam, featuring an open porous structure. A magnified image (the inset in Figure 1 a) discloses a dendritic structure composing of irregularly shaped particles. Meanwhile, IL modification has not induced any




Figure 1. Representative SEM images of a) Cu-Foam and b) Cu-Foam-IL; the insets show magnified images, and the red arrow in the inset of panel (b) marks a curved meniscus of the IL.

pronounced difference in either the morphology or their average macropore sizes ($31.8 \pm 8.1 \mu\text{m}$ vs. $31.7 \pm 8.4 \mu\text{m}$; Figures 1 b and S3). The IL can be seen (the inset in Figure 1 b), existing as blur on the dendritic nanostructures. Characteristic elements of the IL (F, N, and S) can be identified on Cu-Foam-IL using both energy dispersive X-ray spectroscopic (EDS) and X-ray photoelectron spectroscopy (XPS) (Figures S4 & S5), confirming the successful incorporation of the IL in Cu-Foam. To explore the spatial distribution of the IL, EDS elemental mapping analyses were performed (Figure S6). The EDS signals of F and S from the [BMIm][NTf₂], are distributed over the porous Cu foams and surround the macropores without any localized aggregation, suggesting a homogeneous distribution of the IL. To probe any possible change in the surface electronic structure of Cu after IL modification, XPS (Cu 2p_{3/2}) and Auger spectra (Cu LMM) of Cu were recorded (Figure S7). Both samples exhibit a major XPS peak at a binding energy (BE) of 932.5 eV, which associates with Cu⁰/Cu⁺. The Cu LMM Auger spectra confirm that the surface Cu on both samples mainly exists as Cu⁺ (i.e. Cu₂O),^[20] which is not surprising since the oxidation of Cu to Cu₂O occurs immediately upon air exposure.^[21] A minor shoulder peak at a BE of 934.7 eV, which associates with Cu(OH)₂,^[20] can also be observed on pristine Cu-Foam, indicating that a small portion of Cu₂O in Cu-Foam are prone to further oxidation to form Cu(OH)₂. This consequent oxidation process was also reported by Tannenbaum et al. when studying the initial oxidation behavior of Cu in air.^[21] Intriguingly, this shoulder peak is absent on Cu-Foam-IL, implying that the IL can help suppress surface oxidation, which is in line with our previous study on Pt-based catalysts.^[17e-g] Notwithstanding this difference, considering the well documented readiness of copper oxide reduction under CO₂RR conditions,^[10,22] the presence of a small portion of Cu(OH)₂ species on initial Cu-Foam is not expected to play a significant role in altering the product distribution. The CO₂RR performance on Cu is sensitive to surface facets of Cu.^[23] To find out whether the IL can change the Cu surface by selectively blocking certain facets, we performed Pb_{UPD} stripping experiments on both samples (Figure S8). The comparable integrated areas of Pb_{UPD} stripping peaks verify that (selective) blocking of Cu facets by the IL can be ruled out.

The CO₂ electrolysis experiments were performed in a gas-tight electrochemical cell with anode and cathode separated by an anion exchange membrane (Figure S9).

Figure 2a compares the overall current densities of both samples obtained from chronoamperometry experiments at various potentials (Figure S10). Despite the fluctuation, the electrolysis current densities are more or less comparable at the beginning and end of the electrolysis on both samples. This result indicates that Cu foams are stable during the




Figure 2. a) Current densities recorded at various electrolysis potentials, and b) Faradaic efficiency of CO₂RR over Cu-Foam and Cu-Foam-IL at -0.7 V. Electrolysis was performed for 1 hour in 0.1 M CO₂ saturated KHCO₃ solution.

electrolysis regardless of IL modification, which is also evidenced by the intact dendritic structures of both Cu foams after the electrolysis (Figure S11). The stability of the IL on Cu foams during the CO₂RR was also probed by performing post-reaction analyses of Cu-Foam-IL using both XPS and diffuse reflectance infrared Fourier transform spectroscopy techniques. The characteristic signals of IL can be clearly resolved using both techniques after the electrolysis (Figure S12), implying that the IL can be well-maintained within the Cu foams during electrolysis. The overall current densities are comparable between these two samples, despite a slight current increase in Cu-Foam-IL at potentials of -0.7 and -0.8 V versus reversible hydrogen electrode (vs. RHE). These results verify that the presence of the IL has not induced any change in mass transport properties of reactant molecules (CO₂) from bulk electrolyte to Cu-Foam surfaces, and also imply that the majority of the CO₂ molecules may approach the catalyst surface in a free form instead of an IL-coordinated form. Figure 2b compares the FEs of various products on both samples at -0.7 V. A variety of products, including CO, formate, ethylene glycol (EG), ethylene, ethane, ethanol, n-propanol, methane, and acetate can be detected, with CO, formate, and EG identified as the major products (in addition to hydrogen). Various CO₂RR products can usually be observed in Cu foams, while the major product depends on their morphology, active surface area, and foam thickness.^[2b,18,24] Intriguingly, herein we observe that EG, which is usually identified as a minor product in Cu catalysts, is produced with impressively high FEs ($\approx 20\%$) on both samples. These results showcase that Cu foams are a versatile platform in producing value-added CO₂RR products.

The potential dependent FEs of various products on pristine and IL-modified Cu-Foams are compared in Figure 3. The HER, a major competing reaction of the CO₂RR, still dominates the product spectra on both catalysts. A surge in H₂




Figure 3. Summary of the FEs for the CO₂RR products on both Cu-Foam catalysts at different potentials. The suppressed products are marked in red. The arrows emphasize the changes in FEs of the suppressed products.

production is observed at electrode potentials lower than -0.7 V, relating to the liberation of surface sites from adsorbed *CO.^[25] Meanwhile, the HER is promoted by IL

modification. This may stem from the inherent acidity and superior proton transfer capability of the IL being used, which offers greater proton availability for the HER.^[14a,26] The H₂ production rates on both samples converge at lower electrode potentials (< -0.85 V), indicating that at higher reaction rate, the HER is mainly limited by the diffusion of proton (or proton source) from bulk solution to the catalyst surface, and the influence of IL modification is not pronounced. Similar potential-dependent FEs for major CO₂RR products, including formate, EG, CO, ethylene, and ethane, can be observed on both samples despite some minor difference in FEs for EG and formate at around -0.7 V, due to the liberation of strongly adsorbed *CO intermediate from Cu surfaces. Different from other studies of the CO₂RR on Cu catalysts, on which methane is a major product, in the current work, methane is produced with a rather low FE ($< 1\%$) on both catalysts. Similarly, Broekmann et al. also observed that C₁ pathway to methane was almost completely suppressed on Cu foams.^[18] The morphology or surface faceting of Cu catalysts plays a crucial role in determining the product selectivity of CO₂RR.^[27] For instance, Cu(100) facets favor the formation of ethylene while Cu(111) facets facilitate the formation of methane.^[27b] This structure sensitive behavior of the CO₂RR on Cu catalysts originates from the differences in binding energy of *CO and/or energetic barrier for the C–C coupling or hydrogenation step between different Cu facets.^[8b,28] Herein, the low FEs of methane on both catalysts imply that the Cu foams after the initial reduction of surface Cu₂O species during the CO₂RR might be enclosed by abundant Cu(100) facets as suggested by Broekmann et al.^[18,24] The comparable FEs and onset potentials for major products such as CO and formate on Cu-Foam and Cu-Foam-IL also verify that the presence of IL has not induced any fundamental structural change on the Cu foam itself, and at the same time, the possible blockage or surface rearrangement of specific faceting by IL molecules during the CO₂RR can be excluded. The most striking effect induced by IL modification is that ethanol and n-propanol, giving a maximum FE of 7% and 5% on pristine Cu-Foam, respectively, are completely absent on Cu-Foam-IL (Figures 3h and i). Meanwhile, the FE of ethylene is solely suppressed in the high overpotential region (< -0.7 V), with the highest FE decreasing from 10.2% to 5.2% after IL modification (Figure 3d), while little difference can be observed in the low overpotential region (i.e. from -0.6 to -0.7 V). The same conclusion can also be drawn by comparing the partial current densities of CO₂RR products (Figure S13). The IL has selectively slowed down the production rate of ethylene in the high overpotential region and ceased the production of ethanol and n-propanol. These results demonstrate that the feasibility of the IL as a chemical trapping agent, which provides the basis for deducing the CO₂RR pathways by analyzing the altered product spectrum in presence of the IL.

Despite understandings of reaction pathways on Cu catalysts are rife with controversy, some consensus has been reached, which enables discussion of the observed chemical trapping results. Transferring the first electron to CO₂ to form CO₂^{•-} anion is considered as the rate-determining step for CO₂ activation because of the high reorganization energy

needed to activate a linear CO₂ molecule to form CO₂^{•-} anion with bent coordination geometry.^[8d,15,29] Moreover, CO is identified as a key intermediate during the reduction of CO₂ to various C₂₊ products, since CO is the only C₁ molecule that gives similar product spectrum as CO₂ on a Cu catalyst.^[3a,d] However, it remains elusive how the adsorbed CO intermediate is further converted into various products. Intrigued by the altered product spectrum after IL modification, we clarify several elusive reduction pathways by referring to the widely reported yet controversial mechanism in literature, as summarized in Figure 4.

Among various products, ethylene shows the most interesting response to IL modification. Its formation is only suppressed at high overpotentials, while at low overpotentials both FE (Figure 3d) and the partial current density of ethylene (Figure S13d) are almost the same regardless of IL modification. This result strongly suggests that ethylene could form by two separate pathways at high and low overpotentials. A dual pathway mechanism for ethylene production was proposed by Koper et al. when studying CO reduction on Cu.^[28b] One pathway (Pathway II) involves the dimerization of two adjacent CO at low overpotentials, which is later reduced and protonated to form ethylene. The dimerization would proceed by forming a hydrogenated CO dimer (*CO-COH) as confirmed by spectroscopic and theoretical studies.^[8b] On the other pathway (Pathway I), CO is converted into either *CHO^[4a,28b] or *COH^[30] at high overpotentials, which is then reduced to carbene-like *CH₂ species, followed by either C–C coupling between two *CH₂, or CO insertion as in the Fischer–Tropsch process, to produce ethylene.^[30] The dual pathway mechanism may also hold its validity for ethylene production in Cu-Foams. The IL could selectively quench one or more intermediates in Pathway I, which eventually suppresses the formation of ethylene at high overpotentials, while it appears that Pathway II, which starts at relatively low overpotentials and involves the C–C coupling through CO dimerization, is undisturbed by the IL.

Ethane is not a typical CO₂RR product on Cu catalysts.^[31] The production of ethane with a significant FE is explicitly observed on nanostructured porous Cu catalysts.^[31,32] Ethane can be seen as a reduction product of ethylene after two more protonation steps. The porous structure of Cu catalysts seems to increase the retention time of pre-formed products in a confined space. Therefore, for a long time, the formation of ethane has been attributed to the re-adsorption and reduction of pre-formed ethylene on Cu catalysts (Pathways I and II A).^[31,32] However, both FE and partial current density of ethane are actually insensitive to IL modification (Figures 3e and S13e). The entirely different responses of FEs for ethylene and ethane to IL modification imply that ethane is formed via an independent pathway. Recent works report that ethane is produced by the CO dimerization pathway involving ethoxy intermediate,^[33] which reconciles with our observation that the pathway involving CO dimerization is undisturbed by the IL. These findings suggest that production of ethane would mainly proceed through Pathway IIB (Figure 4).

Ethanol is considered to share the similar formation mechanism as ethylene.^[3d,8d] Two reaction pathways, which involve either formation of carbene intermediate (*CH₂)




Figure 4. Proposed reaction roadmaps of CO₂RR on Cu catalysts. Selected intermediates are presented for clarity. Unfeasible pathways are marked by red crosses.

(Pathway I) or dimerization of two adjacent CO (Pathway II), are usually proposed (Figure 4). We found that formation of ethanol is completely suppressed on Cu-Foam-IL, which suggests that IL traps the key intermediate(s) leading to the formation of ethanol. Similarly, n-propanol is not produced on Cu-Foam-IL. It is generally accepted that the formation of n-propanol undergoes intramolecular C–C coupling between CO and hydrogenated carbon (e.g., carbene *CH₂), followed by proton/electron transfer to form propionaldehyde, an intermediate that is further reduced to n-propanol (Figure 4).^[3d,8d,34] It can be seen that the formation of both ethanol and n-propanol involves carbene species (*CH₂), which is also the intermediate to produce ethylene at high overpotentials. The IL-induced suppression of ethanol, n-propanol, and ethylene (at high overpotentials, Pathway I) infers that these products likely share one or more common intermediate(s) selectively trapped by the IL.

Regarding the other CO₂RR products including CO and formate, their differences in FEs and partial current densities are quite minor or within measurement error between two catalysts, determining their pathways conclusively becomes challenging. Nevertheless, some inspiring information can be deduced. For instance, the formation of CO and formate is insensitive to IL modification, indicating that starting from the adsorption of CO₂ on Cu surfaces to the formation of adsorbed CO, the IL seems to play a negligible role, or in other words, the IL does not take effect through coordinating with CO₂ molecules which are more likely transported to the catalysts surface in a free form. Moreover, EG is usually detected as a minor product of the CO₂RR.^[31,35] However,

herein both Cu foam catalysts exhibit fairly high FE of EG: up to 25% and 19% on Cu-Foam and Cu-Foam-IL, respectively. The formation of EG is double-checked by analyzing the liquid products using GC-MS (Figure S14). Consensus on the reaction pathway to EG has not yet been reached, although it is inferred that EG formation might proceed through a CO dimerization mechanism.^[31,35] Herein, EG formation is always accompanied by formate, and their FEs exhibit similar potential-dependent behavior, that is, higher FEs obtained at lower overpotentials and maximum FEs obtained at around –0.7 V. These results imply that these two products probably share the same intermediate, for example, *CO₂[–], which has been experimentally confirmed as a key intermediate to produce formate.^[36] Brennecke et al. suggested that C–C coupling could also take place between two adsorbed CO₂[–] to form oxalate species.^[19a] The hypothesis here is that EG is produced via dimerization of two adsorbed *CO₂[–] species, instead of *CO, followed by multistep reduction and protonation to give EG (Figure 4). The predominant product at –0.7 V switches from EG on Cu-Foam to formate on Cu-Foam-IL. The IL may inhibit the dimerization process of the co-adsorbed CO₂[–] species by preventing their close approach.^[19a] It is also intriguing to observe that IL modification exhibits little impact on the methane formation. Two reaction pathways are usually proposed for the methane formation. One pathway involves carbene (*CH₂) as an intermediate, which is further reduced to *CH₃ and finally to CH₄. The other pathway is through hydrogenation of *CO to form *CHO, followed by a multiple electron-proton transfer process to produce CH₄ (Fig-

ure S15). Considering that Pathway I (carbene pathway) has been significantly suppressed by the IL, herein, comparable FEs of methane on both Cu foams leads us to hypothesize that methane is mainly produced through the latter pathway (Figure 4).

Analyzing the IL-induced change in CO₂RR product distribution provides a unique perspective to gain some unprecedented mechanistic insights into the Cu catalyzed CO₂RR which actually bypasses the necessity of explicit understandings about the chemical identity of surface intermediate(s). Based on the above results, a simplified overview of the reaction pathways that lead to varied CO₂RR products is summarized in Figure 5, where the IL suppressed products and pathways are highlighted in yellow. It is intriguing to observe that the bifurcation of intermediates leading to the suppressed products starts right after the formation of adsorbed carbene (i.e. *CH₂) (Figure 4). This hints that the key intermediate(s) are either *CH₂ or other species (e.g., *COH, *CHO, *C, *CH) that can further be converted to *CH₂ (Figure S16). Another key question is how the IL molecules can trap the surface intermediate(s). IL molecules are reported to adopt a charge-separated layered structure with alternating cation-/anion-rich layer at electrified surfaces.^[17f,37] Accordingly, [BMIm]⁺ cations should be enriched at the innermost (Stern) layer of the electrode-electrolyte interface when the electrode is negatively polarized (i.e. the CO₂ electrolysis conditions). Therefore, understanding of how [BMIm]⁺ cations can possibly interact with other species would be crucial to extrapolate the role of ILs during the CO₂RR. It is well documented that an imidazolium cation can easily be deprotonated at its C2-site, thus converting the C2-site into a reactive center due to its nucleophilicity.^[38] Accordingly, to clarify whether [BMIm]⁺ interacts with surface intermediate(s) via its C2-site, an imidazolium-based IL on which the C2-site at the imidazolium cation ring is “neutralized” by a methyl group (denoted as [BMMIm]⁺, Figure S17a), was used for modifying Cu foams. It turns out that the chemical trapping effect of the IL is not pronounced. Both ethanol and propanol can be detected, and the formation of ethylene at high overpotentials is not suppressed (Figure S18). Furthermore, another IL, [HMIm][NTf₂] which shares structural similarity with [BMIm][NTf₂] but features a longer cationic chain, was also

tested. Although both ethanol and propanol can still be detected, their FEs are much lower than those on unmodified counterpart, and ethylene formation is also suppressed (Figure S18). Two more common ILs (i.e. [MTBD][NTf₂], [P₁₄₄₄][NTf₂]) were also tested for comparison. Not surprisingly, no pronounced chemical trapping effect can be identified using either IL (Figure S18). Their product spectra are comparable to that of the unmodified Cu-Foam, except for a slightly higher FEs of H₂ on Cu-Foam modified with [MTBD][NTf₂], probably due to the protonic nature of this IL. These results lead us to hypothesize that the IL traps the surface key intermediates through bonding with carbene (or other hydrogenated carbon species) on Cu surfaces. This process may involve deprotonation and following alkylation reactions at the C2-site of the imidazolium ring.^[39]

Conclusion

This work outlines a new strategy to probe CO₂RR pathways. The IL alters the product spectrum during the CO₂RR on Cu foams. Analyzing the responses of CO₂RR products to IL modification is a unique way to gain new insights into CO₂RR pathways: 1) Ethanol and n-propanol form explicitly through a “carbene” mechanism, while formation of ethylene could proceed through two independent pathways which involve carbene and dimerized CO as key intermediates at high and low overpotentials, respectively; 2) The presence of the IL can selectively suppress the formation of those products involving carbene intermediates, likely by forming stable imidazolium-carbene compound(s); 3) Ethane, which has long been considered a reduction product of re-adsorbed ethylene during CO₂RR, is identified as proceeding with an independent pathway that involves CO dimerization process. Considering the great structural flexibility in ILs, identification of reaction pathways for CO₂ products by carefully designing task-specific ILs to selectively interact with intermediate species may be feasible. The success of this will bring IL modification closer to being a generic strategy for analyzing complicated CO₂ reduction pathways. This approach is transferable to other electrocatalytic reactions and materials. This work demonstrates the possibility of moderating the CO₂RR product spectrum by rationally leveraging the IL modification effect, which can be key to finely tuning the catalytic properties of a CO₂ reduction catalyst at a molecular level.

Acknowledgements

The authors acknowledge the funding from the European Research Council (ERC) under the European Union’s Horizon 2020 research and innovation program (grant agreement No. 681719). We thank Dr. Marc Ledendecker for his comments and suggestions on the manuscript. We also thank Prof. Hongbin Zhang, Mr. Yi Xiao and Prof. Bo Li for fruitful discussions. Open access funding enabled and organized by Projekt DEAL.




Figure 5. A simplified diagram summarizing the proposed CO₂RR pathways on Cu. The IL suppressed pathways and products are highlighted in yellow.

Conflict of interest

The authors declare no conflict of interest.

Keywords: CO₂ reduction · copper · foams · ionic liquids · reaction mechanisms

- [1] a) C. Costentin, M. Robert, J. M. Saveant, *Chem. Soc. Rev.* **2013**, 42, 2423–2436; b) J. L. Qiao, Y. Y. Liu, F. Hong, J. J. Zhang, *Chem. Soc. Rev.* **2014**, 43, 631–675; c) P. Strasser, M. Glichi, S. Kuehl, T. Moeller, *Chem. Soc. Rev.* **2018**, 47, 715–735.
- [2] a) C. Reller, R. Krause, E. Volkova, B. Schmid, S. Neubauer, A. Rucki, M. Schuster, G. Schmid, *Adv. Energy Mater.* **2017**, 7, 1602114; b) K. Klingan, T. Kottakkat, Z. P. Jovanov, S. Jiang, C. Pasquini, F. Scholten, P. Kubella, A. Bergmann, B. Roldan Cuenya, C. Roth, H. Dau, *ChemSusChem* **2018**, 11, 3449–3459; c) S. Gao, Y. Lin, X. Jiao, Y. Sun, Q. Luo, W. Zhang, D. Li, J. Yang, Y. Xie, *Nature* **2016**, 529, 68–71; d) K. Jiang, R. B. Sandberg, A. J. Akey, X. Liu, D. C. Bell, J. K. Nørskov, K. Chan, H. Wang, *Nat. Catal.* **2018**, 1, 111–119; e) H. Xiao, W. A. Goddard III, T. Cheng, Y. Liu, *Proc. Natl. Acad. Sci. USA* **2017**, 201702405.
- [3] a) Y. Hori in *Modern Aspects of Electrochemistry*, Vol. 42 (Eds.: C. G. Vayenas, R. E. White, M. E. Gamboa-Aldeco), Springer New York, New York, **2008**, pp. 89–189; b) H. Yoshio, K. Katsuchi, S. Shin, *Chem. Lett.* **1985**, 14, 1695–1698; c) Y. Hori, H. Wakebe, T. Tsukamoto, O. Koga, *Electrochim. Acta* **1994**, 39, 1833–1839; d) Y. Hori, R. Takahashi, Y. Yoshinami, A. Murata, *J. Phys. Chem. B* **1997**, 101, 7075–7081; e) P. De Luna, R. Quintero-Bermudez, C.-T. Dinh, M. B. Ross, O. S. Bushuyev, P. Todorović, T. Regier, S. O. Kelley, P. Yang, E. H. Sargent, *Nat. Catal.* **2018**, 1, 103–110.
- [4] a) A. A. Peterson, F. Abild-Pedersen, F. Studt, J. Rossmeisl, J. K. Nørskov, *Energy Environ. Sci.* **2010**, 3, 1311–1315; b) A. A. Peterson, J. K. Nørskov, *J. Phys. Chem. Lett.* **2012**, 3, 251–258.
- [5] Y. Y. Birdja, E. Pérez-Gallent, M. C. Figueiredo, A. J. Göttele, F. Calle-Vallejo, M. T. M. Koper, *Nat. Energy* **2019**, 4, 732–745.
- [6] a) A. D. Handoko, F. Wei, Jenndy, B. S. Yeo, Z. W. Seh, *Nat. Catal.* **2018**, 1, 922–934; b) T.-C. Chou, C.-C. Chang, H.-L. Yu, W.-Y. Yu, C.-L. Dong, J.-J. Velasco-Vélez, C.-H. Chuang, L.-C. Chen, J.-F. Lee, J.-M. Chen, H.-L. Wu, *J. Am. Chem. Soc.* **2020**, <https://doi.org/10.1021/jacs.9b11126>; c) Y. Zheng, A. Vasileff, X. Zhou, Y. Jiao, M. Jaroniec, S.-Z. Qiao, *J. Am. Chem. Soc.* **2019**, 141, 7646–7659; d) S. Zhu, T. Li, W.-B. Cai, M. Shao, *ACS Energy Lett.* **2019**, 4, 682–689.
- [7] B. D. Smith, D. E. Irish, P. Kedzierzawski, J. Augustynski, *J. Electrochem. Soc.* **1997**, 144, 4288–4296.
- [8] a) R. Kortlever, J. Shen, K. J. P. Schouten, F. Calle-Vallejo, M. T. M. Koper, *J. Phys. Chem. Lett.* **2015**, 6, 4073–4082; b) E. Pérez-Gallent, M. C. Figueiredo, F. Calle-Vallejo, M. T. M. Koper, *Angew. Chem. Int. Ed.* **2017**, 56, 3621–3624; *Angew. Chem.* **2017**, 129, 3675–3678; c) K. D. Yang, C. W. Lee, K. Jin, S. W. Im, K. T. Nam, *J. Phys. Chem. Lett.* **2017**, 8, 538–545; d) Z. Sun, T. Ma, H. Tao, Q. Fan, B. Han, *Chem* **2017**, 3, 560–587.
- [9] R. Kas, O. Ayemoba, N. J. Firet, J. Middelkoop, W. A. Smith, A. Cuesta, *ChemPhysChem* **2019**, 20, 2904–2925.
- [10] S. Jiang, K. Klingan, C. Pasquini, H. Dau, *J. Chem. Phys.* **2019**, 150, 041718.
- [11] H. Y. Wang, J. P. Liu, J. K. Fu, H. B. Zhang, K. R. Tsai, *Res. Chem. Intermed.* **1992**, 17, 233–242.
- [12] a) J. G. Ekerdt, A. T. Bell, *J. Catal.* **1980**, 62, 19–25; b) J. A. Baker, A. T. Bell, *J. Catal.* **1982**, 78, 165–181.
- [13] a) J. Feng, S. Zeng, J. Feng, H. Dong, X. Zhang, *Chin. J. Chem.* **2018**, 36, 961–970; b) G.-R. Zhang, B. J. M. Etzold, *J. Energy Chem.* **2016**, 25, 199–207; c) M. Alvarez-Guerra, J. Albo, E. Alvarez-Guerra, A. Irabien, *Energy Environ. Sci.* **2015**, 8, 2574–2599; d) S. J. Zhang, J. Sun, X. C. Zhang, J. Y. Xin, Q. Q. Miao, J. J. Wang, *Chem. Soc. Rev.* **2014**, 43, 7838–7869.
- [14] a) J. H. Koh, H. S. Jeon, M. S. Jee, E. B. Nursanto, H. Lee, Y. J. Hwang, B. K. Min, *J. Phys. Chem. C* **2015**, 119, 883–889; b) B. A. Rosen, A. Salehi-Khojin, M. R. Thorson, W. Zhu, D. T. Whipple, P. J. A. Kenis, R. I. Masel, *Science* **2011**, 334, 643–644.
- [15] B. A. Rosen, I. Hod, *Adv. Mater.* **2018**, 30, 1706238.
- [16] U. Kernchen, B. Etzold, W. Korth, A. Jess, *Chem. Eng. Technol.* **2007**, 30, 985–994.
- [17] a) J. Snyder, T. Fujita, M. W. Chen, J. Erlebacher, *Nat. Mater.* **2010**, 9, 904–907; b) Y. M. Tan, C. F. Xu, G. X. Chen, N. F. Zheng, Q. J. Xie, *Energy Environ. Sci.* **2012**, 5, 6923–6927; c) J. Snyder, K. Livi, J. Erlebacher, *Adv. Funct. Mater.* **2013**, 23, 5494–5501; d) G.-R. Zhang, M. Munoz, B. J. Etzold, *ACS Appl. Mater. Interfaces* **2015**, 7, 3562–3570; e) G.-R. Zhang, M. Munoz, B. J. Etzold, *Angew. Chem. Int. Ed.* **2016**, 55, 2257–2261; *Angew. Chem.* **2016**, 128, 2298–2302; f) G.-R. Zhang, T. Wolker, D. J. S. Sandbeck, M. Munoz, K. J. J. Mayrhofer, S. Cherevko, B. J. M. Etzold, *ACS Catal.* **2018**, 8, 8244–8254; g) M. George, G.-R. Zhang, N. Schmitt, K. Brunnengraber, D. J. S. Sandbeck, K. J. J. Mayrhofer, S. Cherevko, B. J. M. Etzold, *ACS Catal.* **2019**, 9, 8682–8692.
- [18] A. Dutta, M. Rahaman, N. C. Luedi, M. Mohos, P. Broekmann, *ACS Catal.* **2016**, 6, 3804–3814.
- [19] a) L. Y. Sun, G. K. Ramesha, P. V. Kamat, J. F. Brennecke, *Langmuir* **2014**, 30, 6302–6308; b) Z. G. Lei, C. N. Dai, B. H. Chen, *Chem. Rev.* **2014**, 114, 1289–1326.
- [20] M. C. Biesinger, *Surf. Interface Anal.* **2017**, 49, 1325–1334.
- [21] I. Platzman, R. Brener, H. Haick, R. Tannenbaum, *J. Phys. Chem. C* **2008**, 112, 1101–1108.
- [22] a) L. Mandal, K. R. Yang, M. R. Motapothula, D. Ren, P. Lobaccaro, A. Patra, M. Sherburne, V. S. Batista, B. S. Yeo, J. W. Ager, J. Martin, T. Venkatesan, *ACS Appl. Mater. Interfaces* **2018**, 10, 8574–8584; b) D. Ren, Y. Deng, A. D. Handoko, C. S. Chen, S. Malkhandi, B. S. Yeo, *ACS Catal.* **2015**, 5, 2814–2821.
- [23] Y. Huang, A. D. Handoko, P. Hirunsit, B. S. Yeo, *ACS Catal.* **2017**, 7, 1749–1756.
- [24] S. Sen, D. Liu, G. T. R. Palmore, *ACS Catal.* **2014**, 4, 3091–3095.
- [25] D. Raciti, C. Wang, *ACS Energy Lett.* **2018**, 3, 1545–1556.
- [26] Q. Wang, Y. Gao, Z. Ma, Y. Zhang, W. Ni, H. A. Younus, C. Zhang, Z. Chen, S. Zhang, *J. Energy Chem.* **2020**, 150, 041718.
- [27] a) W. Tang, A. A. Peterson, A. S. Varela, Z. P. Jovanov, L. Bech, W. J. Durand, S. Dahl, J. K. Nørskov, I. Chorkendorff, *Phys. Chem. Chem. Phys.* **2012**, 14, 76–81; b) A. Loiudice, P. Lobaccaro, E. A. Kamali, T. Thao, B. H. Huang, J. W. Ager, R. Buonsanti, *Angew. Chem. Int. Ed.* **2016**, 55, 5789–5792; *Angew. Chem.* **2016**, 128, 5883–5886; c) D. Gao, I. Sinev, F. Scholten, R. M. Arán-Ais, N. J. Divins, K. Kvashnina, J. Timoshenko, B. Roldan Cuenya, *Angew. Chem. Int. Ed.* **2019**, 58, 17047–17053; *Angew. Chem.* **2019**, 131, 17203–17209.
- [28] a) J. H. Montoya, C. Shi, K. Chan, J. K. Nørskov, *J. Phys. Chem. Lett.* **2015**, 6, 2032–2037; b) K. J. P. Schouten, Z. Qin, E. Pérez-Gallent, M. T. M. Koper, *J. Am. Chem. Soc.* **2012**, 134, 9864–9867.
- [29] a) A. Hailu, S. K. Shaw, *Energy Fuels* **2018**, 32, 12695–12702; b) W. Lu, B. Jia, B. Cui, Y. Zhang, K. Yao, Y. Zhao, J. Wang, *Angew. Chem. Int. Ed.* **2017**, 56, 11851–11854; *Angew. Chem.* **2017**, 129, 12013–12016.
- [30] X. Nie, M. R. Esopi, M. J. Janik, A. Asthagiri, *Angew. Chem. Int. Ed.* **2013**, 52, 2459–2462; *Angew. Chem.* **2013**, 125, 2519–2522.
- [31] S. Nitopi, E. Bertheussen, S. B. Scott, X. Liu, A. K. Engstfeld, S. Horch, B. Seger, I. E. L. Stephens, K. Chan, C. Hahn, J. K. Nørskov, T. F. Jaramillo, I. Chorkendorff, *Chem. Rev.* **2019**, 119, 7610–7672.
- [32] a) K. D. Yang, W. R. Ko, J. H. Lee, S. J. Kim, H. Lee, M. H. Lee, K. T. Nam, *Angew. Chem. Int. Ed.* **2017**, 56, 796–800; *Angew. Chem.* **2017**, 129, 814–818; b) H. Song, M. Im, J. T. Song, J.-A.

- Lim, B.-S. Kim, Y. Kwon, S. Ryu, J. Oh, *Appl. Catal. B* **2018**, 232, 391–396; c) C. S. Chen, J. H. Wan, B. S. Yeo, *J. Phys. Chem. C* **2015**, 119, 26875–26882.
- [33] a) M. Ma, K. Djanashvili, W. A. Smith, *Angew. Chem. Int. Ed.* **2016**, 55, 6680–6684; *Angew. Chem.* **2016**, 128, 6792–6796; b) A. Vasileff, Y. Zhu, X. Zhi, Y. Zhao, L. Ge, H. M. Chen, Y. Zheng, S. Z. Qiao, *Angew. Chem. Int. Ed.* **2020**, <https://doi.org/10.1002/anie.202004846>; *Angew. Chem.* **2020**, <https://doi.org/10.1002/ange.202004846>.
- [34] a) D. Kim, C. S. Kley, Y. Li, P. Yang, *Proc. Natl. Acad. Sci. USA* **2017**, 114, 10560–10565; b) D. Ren, N. T. Wong, A. D. Handoko, Y. Huang, B. S. Yeo, *J. Phys. Chem. Lett.* **2016**, 7, 20–24; c) R. A. Geioushy, M. M. Khaled, K. Alhooshani, A. S. Hakeem, A. Rinaldi, *Electrochim. Acta* **2017**, 245, 456–462.
- [35] K. P. Kuhl, E. R. Cave, D. N. Abram, T. F. Jaramillo, *Energy Environ. Sci.* **2012**, 5, 7050–7059.
- [36] I. V. Chernyshova, P. Somasundaran, S. Ponnuram, *Proc. Natl. Acad. Sci. USA* **2018**, 115, E9261–E9270.
- [37] R. Wen, B. Rahn, O. M. Magnussen, *Angew. Chem. Int. Ed.* **2015**, 54, 6062–6066; *Angew. Chem.* **2015**, 127, 6160–6164.
- [38] K. Noack, P. S. Schulz, N. Paape, J. Kiefer, P. Wasserscheid, A. Leipertz, *Phys. Chem. Chem. Phys.* **2010**, 12, 14153–14161.
- [39] E. Ennis, S. Handy, *Molecules* **2009**, 14, 2235–2245.

Manuscript received: July 9, 2020

Accepted manuscript online: July 22, 2020

Version of record online: September 3, 2020